ITEM	TOTAL	UNIT	DESCRIPTION
			ROADWAY
E-8	95	Sq Yd.	Removal & Disposal of Pavement
L-9	3580	Sq Yd.	Seeding and Protection
L-9	0.37	Tons	Commercial Fertilizer
			DRAINAGE
E-3	200	Cu.Yd.	Channel Excavation
I-1	230	Lin.Ft	96" Pipe Class A-1 Sec. M-6.6a
I-1	12	Lin Ft	60" Pipe Class B-1
I-1	1340	Lin Ft	54" Pipe Class B-1
I-2	29	Cu.Yd.	Concrete Headwalls
I-5	2	Each	45°-54" Pipe Class B-1 Specials
I-8	1	Each	Standard Nº 1-A Manhole Modified As Per Plan
I-8	2	Each	Standard Nº 2-5 Catch Basin Modified As Per Plan
I-10	70	Sq Yd.	6" Reinforced Concrete Riprap
I-21	15	Sq Yd	Portland Cement Concrete Median As Per Plan
S-4	788	Lbs.	Reinforcing Steel
S-24	1	Each	Removal Headwall, Catch Basin & Tile
S-24	1	Each	Plug Tile
			PAVEMENT
B-70	95	Sq Yd.	9" Concrete Pavement
B-35	6.60	Cu Yd.	Asphaltic Concrete Leveling Course
T-30	40	Gal	Bituminous Tack Coat
T-35	6.60	Cu Yd	Asphaltic Concrete Wearing Course
I-3	Lump	Lump	Maintain Traffic

TRAFFIC NOTE

Continous two-way traffic shall be maintained at all times. The maintenance and protection of traffic shall be as directed by the O.S.D.H. Division 2 Traffic Engineer.

The Standard Specifications of the State of Ohio, Department of Highways including changes and supplemental specifications listed in the proposal shall govern this improvement as provided in the 1964 Specifications.