PAVING AND DRAINAGE PLAN
FOR
BELMONT FARMS, PLAT 2
WOOD COUNTY, OHIO

GENERAL SUMMARY

ITEM	QUANTITY	UNIT	DESCRIPTION
			PAVEMENT
404	175	Cu. Yds.	1" Asphalt Concrete (70-85) (Surface)
402	263	Cu. Yds.	1 1/2" Asphalt Concrete (Leveling)
408	2,205	Gal.	Bituminous Prime Coat (C.35 Gal. per sq. yd.)
304	1,050	Cu. Yds.	6" Aggregate Base Course
605	4,828	Lin. Ft.	6" Shallow Pipe Underdrain
609	5,316	Lin. Ft.	6" Combined Curb & Gutter (Mountable Type)
203	7,741	Sq. Yds.	Subgrade Preparation
203	5,948	Cu. Yds.	Excavation
203	7,440	Cu. Yds.	Embankment Construction, including borrow.
310	1,150	Cu. Yds.	4" Subbase
202	1	Each	Adjust exist. San. M.H. to grade w/H-3 Frame & Cover or equal
405	3.7	Cu. Yds.	4" Bituminous Cold Mix
			DRAINAGE
		Note:	All Pipe To Be Laid With Class "B" Bedding
603	127	Lin. Ft.	12" Conduit Type "B"
603	24	Lin. Ft.	12" Conduit Type "C"
603	34	Lin. Ft.	15" Conduit Type "B"
603	348	Lin. Ft.	15" Conduit Type "C"
603	673	Lin. Ft.	18" Conduit Type "B"
603	252	Lin. Ft.	21" Conduit Type "C"
603	520	Lin. Ft.	24" Conduit Type "C"
604	11	Each	Type A-2 Catch Basin
604	11	Each	Type L-1 Manhole
604	2	Each	Type L-3 Manhole
605	27	Lin. Ft.	24" Conduit Type "D" (707.01)
601	7.5	Sq. Yds.	Dumped Rock Channel Protection (601.08)
	1	Each	Adjust San. M.H. to grade

GENERAL NOTES

All work on this project shall conform to the standards and Specifications of Wood County, Ohio, and/or the State of Ohio Department of Highways Construction and Materials Specifications dated January 1, 1967.

All work performed within the scope of this project is subject to the inspection and approval of Wood County, Ohio.

All surplus excavation shall be placed on the property of the Nicholas Corporation in a location designated by the Engineer.

All catch basins are to be constructed without sumps or traps.

Any Roadways damaged by the Contractor during construction shall be restored to their original condition, and meet the approval of the Engineer.

All public, private utility companies, and the Wood County Engineer's Office, shall be notified in writing by the Contractor at least seven (7) days in advance of beginning any construction operations.

Granular material shall meet the requirements of Section 310.02 of the State of Ohio Department of Highways Construction and Material Specifications dated January 1, 1967.

Inspection will be provided by Wood County Engineer and paid for by the Contractor at the rate of $7.00 /hour. All sewer pipe located in the right of way shall be backfilled with granular material, and shall meet the requirements of Section 603.08.



APPROVED

Max L. Rutherford
COUNTY ENGINEER
WOOD COUNTY, OHIO

DATE Sept 30 1968

APPROVED
COUNTY COMMISSIONERS, WOOD COUNTY, OHIO.

PORTER W. McDONNELL & ASSOCIATES, INC.

CONSULTING ENGINEERS
200 COLTON BUILDING
TOLEDO

1/6