FOR

# The Village at Riverbend Plat Four

MIDDLETON TOWNSHIP, WOOD COUNTY, OHIO

#### INDEX OF SHEETS

TITLE SHEET	1
GENERAL NOTES, SPECIFICATIONS & DETAILS	2 - 3
DRAINAGE WATERSHEDS AND CONTOURS	

## GENERAL SUMMARY

ITEM	QTY.	UNIT	DESCRIPTION		
EROSION CONTROL					
SPEC.	LUMP	LUMP	TEMPORARY CONSTRUCTION ENTRANCE, AS PER PLAN		
SPEC.	LUMP	LUMP	CONCRETE WASHOUT AREA		
832	40	FT.	INLET PROTECTION FILTER FABRIC FENCE		
832	2550	FT.	PERIMETER FILTER FABRIC FENCE		
SPEC.	4	EACH	CURB INLET PROTECTION		
832	29,780	SQ. YD.	CONSTRUCTION SEEDING AND MULCHING		
659	3224	SQ. YD.	PERMANENT SEEDING AND MULCHING		
659	0.29	TONS	COMMERCIAL FERTILIZER (12-12-12) (20 LBS./1,000 SQ. FT.)		
659	8705	GAL	WATERING		

#### BENCH MARK DATA

#### SITE BENCH MARK #200


NORTH RIM OF MONUMENT BOX AT THE CENTERLINE OF HIGH MEADOWS LANE AND 50.3' NORTH OF THE CENTERLINE OF ROACHTON ROAD.

### SITE BENCH MARK #201

"X" CUT ON WEST END OF HEADWALL, 7.2' SOUTH OF THE CENTERLINE OF ROACHTON ROAD AND 662.2' WEST OF THE CENTERLINE OF HIGH MEADOWS LANE.

#### CONVENTIONAL SIGNS

	PROPOSED	EXISTING
SANITARY SEWER	s	s
STORM SEWER	ST	st
WATERLINE		
SANITARY MANHOLE	•	§
STORM MANHOLE	•	🗊
CATCH BASIN		СВ
YARD BASIN	•	📵
WATER VALVE IN MANHOLE	•	W
HYDRANT		~
CENTERLINE		
TYPE B MONUMENT		👁



LOCATION MAP



#### DEVELOPED BY:

McCARTHY RIVERBEND, LLC 3618 KING ROAD, SUITE C TOLEDO, OHIO 43617 419-476-1474

#### SITE DESCRIPTION AND DATA:

	A.	TYPE OF CONSTRUCTION:	SINGLE FAMILY RESIDENTIAL
		SITE PLAT AREA:	8.12 Ac.
B.	В.	AREA DISTURBED:	8.17 Ac.
		PRE-CONSTRUCTION RUNOFF COEFFICIENT:	
L'	<u>ل</u> .	POST-CONSTRUCTION RUNOFF COEFFICIENT	Γ: 0.55
	D.	IMPERVIOUS AREA:	2.44 Ac.
	U.	% IMPERVIOUS AFTER CONSTRUCTION:	30%
	E.	SOIL TYPE:	HoA - HOYTVILLE CLAY LOAM
	F.	PRIOR LAND USE:	AGRICULTURAL
	H.	RECEIVING STREAM:	ROACHTON ROADSIDE DITCH
		TC	GRASSY CREEK TO MAUMEE RIVER

#### IMPLEMENTATION SCHEDULE

- CONTACT STORMWATER COORDINATOR/WOOD COUNTY
- ENGINEER'S OFFICE PRIOR TO DISTURBANCE INSTALL GRAVEL CONSTRUCTION ENTRANCE.
- CLEAR AND GRUB SITE.
- INSTALL EROSION CONTROL MEASURES WITHIN 7 DAYS

- 11. INSTALL CONSTRUCTION AND PERMANENT SEEDING AND MULCHING OVER ALL DISTURBED AREAS PER NOTES ON
- 12. REMOVE EROSION CONTROL MEASURES.
- 14. SINGLE FAMILY LOT EROSION CONTROL
- 15. HOUSE CONSTRUCTION.
- 16. FINAL SEED AND LANDSCAPE LOT. 17. DEVELOPER TO SUBMIT N.O.T.

NO SURFACE WATER SHALL BE ALLOWED TO RUN OFF THE SITE. UNTIL FINAL GRADING IS COMPLETED, THE CONTRACTOR SHALL DIVERT ALL SURFACE WATER TO REMAIN ON SITE: AND MAINTAIN ALL TEMPORARY SEDIMENT AND EROSION CONTROL FEATURES.

#### APPROVED BY

06.25.2018 DATE WOOD COUNTY ENGINEER

THE ABOVE SIGNATURE CONSTITUTES ACKNOWLEDGEMENT THAT THOSE ITEMS OUTLINED IN THE CURRENT EDITION OF THE "WOOD COUNTY SUBDIVISION AND SITE IMPROVEMENT MANUAL" OR AS AMENDED BY THE WOOD COUNTY ENGINEER, HAVE BEEN UTILIZED. TECHNICAL CORRECTNESS AND INTERPRETATION OF THOSE ITEMS CONTAINED WITHIN THE MANUAL REMAIN THE RESPONSIBILITY OF THE ENGINEER PREPARING THE PLANS. THE ABOVE SIGNATURE IS VALID FOR 18 MONTHS FROM THE DATE OF SIGNING.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

END

RIVERBE UR

SHEET

6-1-18

DATE